

STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

Environment department, Room No. 217, 2nd floor, Mantralaya, Annexe, Mumbai- 400 032. Date:October 26, 2018

To.

Mr Pratik Saraogi, M/s. Goldbricks Infrastructure Pvt. Ltd.Address: Anandam World city, Model mill square, Old Umred road, Ganeshpeth Nagpur - 440018 Telephone No.0712 - 2722660 Mobile No.+91 9890990003 Email ID:pratik.saraogi@goldbricks.co.in,

at C.S. No. 101/1 Sheet No. 259, 260, 269, 270 & 271, Mouze Nagpur

Subject: Environment Clearance for Expansion Construction, "Residential & Commercial Development

Sir,

This has reference to your communication on the above mentioned subject. The proposal was considered as per the EIA Notification - 2006, by the State Level Expert Appraisal Committee-III, Maharashtra in its 68th meeting and recommend the project for prior environmental clearance to SEIAA. Information submitted by you has been considered by State Level Environment Impact Assessment Authority in its 139th meetings.

2. It is noted that the proposal is considered by SEAC-III under screening category 8 (b) B1 as per EIA Notification 2006.

Brief Information of the project submitted by you is as below:-

1.Name of Project	"Anandam World City"			
2.Type of institution	Green Building			
3.Name of Project Proponent	Mr Pratik Saraogi, M/s. Goldbricks Infrastructure Pvt. Ltd.Address: Anandam World city, Model mill square, Old Umred road, Ganeshpeth Nagpur - 440018 Telephone No.0712 - 2722660 Mobile No.+91 9890990003 Email ID:pratik.saraogi@goldbricks.co.in,			
4.Name of Consultant	Ultra-Tech (Environmental Consultancy & Laboratory)			
5.Type of project	Mixed use development			
6.New project/expansion in existing project/modernization/diversification in existing project	Expansion			
7.If expansion/diversification, whether environmental clearance has been obtained for existing project	EC received vide SEAC 2010/CR. 128/TC.2 dated 16.10.10, Revalidation of EC dated 12.12.15 for further 7 years			
8.Location of the project	C.S. No. 101/1 Sheet No. 259, 260, 269, 270 & 271, Mouze Nagpur			
9.Taluka	Nagpur			
10.Village	Nagpur			
11.Whether in Corporation / Municipal / other area	Nagpur Municipal Corporation			

SEIAA Meeting No: 139 Meeting Date: September 28, 2018 (SEIAA-STATEMENT-0000000323) SEIAA-MINUTES-0000000641 SEIAA-EC-0000000459

Page 1 of 14 | Secretary S

	Part sanctioned received for FSI area 1,47,550.23 m2 as vide Bldg. permit no. 02/BP/Nagpur/TP/NMC/163 dated 07.04.2012 Part sanctioned received for FSI area 93042.41m2 as vide Bldg. permit no. 259/BP/Nagpur/TP/NMC/1412 dated 28.05.2010 Occupancy certificate: 1) ABC - NMC/TPD/01/occupancy/part dated 28.08.14 2) D - NMC/TPD/Occ, certificate/ 2.6/P.No. 41/111 dated 10.11.15 3) E - NMC/TPD/Occ. Certificate part 20.6/PNo.41/108 dated 7.08.15 F- NMC/TPD/occ.certificate(part)/20.6/PNo.41/109 date			
12.IOD/IOA/Concession/Plan Approval Number	IOD/IOA/Concession/Plan Approval Number: Part sanctioned received for FSI area 1,47,550.23 m2 as vide Bldg. permit no. 02/BP/Nagpur/TP/NMC/163 dated 07.04.2012 Part sanctioned received for FSI area 93042.41m2 as vide Bldg. permit no. 259/BP/Nagpur/TP/NMC/1412 dated 28.05.2010 Occupancy certificate : 1) ABC - NMC/TPD/01/occupancy/part dated 28.08.14 2) D - NMC/TPD/Occ, certificate/ 2.6/ P.No. 41/111 dated 10.11.15 3) E - NMC/TPD/Occ. Certificate part 20.6/PNo.41/108 dated 7.08.15 F-NMC/TPD/occ.certificate(part)/20.6/PNo.41/109 date			
	Approved Built-up Area: 147550			
13.Note on the initiated work (If applicable)	1) EC received vide SEAC 2010/CR. 128/TC.2 dated 16.10.10, Revalidation of EC dated 12.12.15 2) 6 Towers (B+G+19) completed as per local body approval. 2 tower work in progress, 20 villas completed 3) Violation withdrawal received vide letter no. SEAC 2212/CR498/TCII			
14.LOI / NOC / IOD from MHADA/ Other approvals (If applicable)	Not Applicable			
15.Total Plot Area (sq. m.)	1,17,257.00			
16.Deductions	15,257.13			
17.Net Plot area	1,01,999.88			
	FSI area (sq. m.): 2,06,179.09 m2 (Constructed- 56,512.70 m2 Proposed- 1,49,666.39 m2)			
	Non FSI area (sq. m.): 2,73,193.00m2(Constructed- 87,988.48 m2 Proposed- 1,85,204.52 m2)			
Non-FSI)	Total BUA area (sq. m.): 4,79,372.00m2 (Constructed- 1,44,501.18 m2 Proposed- 3,34,870.82 m2)			
10.00	Approved FSI area (sq. m.):			
18 (b).Approved Built up area as per DCR	Approved Non FSI area (sq. m.):			
	Date of Approval:			
19.Total ground coverage (m2)	66,534 m2			
20.Ground-coverage Percentage (%) (Note: Percentage of plot not open to sky)	57			
21.Estimated cost of the project	7750000000			
	7// / 3 1/ 9 1/1 2 3 70/ 9			

	22.Production Details								
Serial Number	Pro	duct	Existing	(MT/M)	Proposed (MT/M)	Total (MT/M)			
1	Not ap	plicable Not app		plicable	Not applicable	Not applicable			
		2	3.Tota	l Wate	r Requiremen	t			
		Source of v	water	NagpurMu	nicipal Corporation				
		Fresh wate	er (CMD):	1079					
		Recycled w Flushing (554					
		Recycled w Gardening	(CMD):	255	HATEM				
		Swimming make up (Cum):	4	Tefan Ozw				
Dry season:		Total Wate Requireme		1892		3			
		Fire fightin Undergrou tank(CMD)	nd water	Residential	500 Commercial 400				
		Fire fightin Overhead v tank(CMD)	water	25					
		Excess trea	~~	380	TE TE	X			
		Source of v	1/2	NagpurMunicipal Corporation					
		Fresh water	1 72): 1079					
		Recycled w	CMD):	554					
		Recycled w Gardening	(CMD):		Jan Dan				
		Swimming make up (Cum):	4444	Mary				
Wet season:		Total Wate Requireme	ent (CMD)	1637	mont	of			
		Fire fightin Undergroutank(CMD)	nd water):	Residential	500 Commercial 400	UI			
			ng - water):	25a rashtra					
Excess treated water			635						
• Dimension of Swimmin • Total water Requirement for • Water requirement for • Details of Plant & Mac Sand Filter Carbon Filter Hair Filter Disinfection (Chlorination Pumping set Capital Cost: Rs. 37.00 I O & M cost: - Rs. 1.8 La		ent in KLD: r make up in chinery used on)	312	ing pool water:					

Shri. Anil Diggikar (Member Secretary SEIAA)

Page 3 of 14

		24	.Detail	s of Total	l water co	nsume	d			
Particula rs	Cons	umption (CM	D)	Loss (CMD)			Ef	fluent (CMD)		
Water Require ment	Existing	Proposed	Total	Existing	Proposed	Total	Existing	Proposed	Total	
Fresh water requireme nt	211	868	1079	32	130	162	179	738	917	
Domestic	106	448	554	0	0	0	106	448	554	
Gardening	62	193	255	0	0	0	0	0	0	
			N	ut ())]	III Itw	7				
		Level of the water table:	Ground	6 to 6.5 mtrs	s depth from G					
		Size and no otank(s) and Quantity:	of RWH	NO	279	801	3			
		Location of t tank(s):	he RWH	near Tower	A & D	3	8			
25.Rain V	Vator	Quantity of r pits:	echarge	6 Tanks of R	Residential +21	no tanks o	f commercial	with 3 bores e	each	
Harvestin (RWH)		Size of recha	rge pits	12m x 7m x4m						
(IXVII)		Budgetary al (Capital cost		Rs 84.00Lacs						
		Budgetary al (O & M cost)		Rs 2.5 Lacs/year						
		Details of UC if any :	GT tanks	Domestic UG tank Capacity (cum): Residential: 1125 + 500 + Commercial: 340 Flushing tank Capacity(cum) Residential 250 Commercial 340 Fire UG tank Capacity (cum) Residential 250 Commercial 400 Irrigation (KLD) 125						
		Natural wate	er	27 - 12 - 1	.1			r		
26.Storm	waten	drainage pat		North to south						
drainage	water	Quantity of s water:	torm	35177m3						
		Size of SWD:		400 mm&250 mm						
			2 I I		<u> </u>					
		Sewage gene in KLD:	ration	1471						
		STP technolo	ogy:	MBBR						
27.Sewage and		Capacity of S (CMD):	TP	3 no. commercial 550, Residential 530 & 630 m3 (For library waste generation will be 1.8 Cum which will be collected in septic tank & then connected to NMC sewer line)						
Waste w	9	Location & a the STP:	rea of	530 KLD in 3	530 KLD in Basement					
		Budgetary al (Capital cost		Rs. 194.20 I	_acs					
		Budgetary al (O & M cost)		Rs. 39.42 Lacs/annum						

Page 4 of 14 Secret

	28.Solie	d waste Management
Waste generation in	Waste generation:	94Kg/Day Excavation – 48795 cum
the Pre Construction and Construction phase:	Disposal of the construction waste debris:	13,197 CUM will be used for filling.
	Dry waste:	3571
	Wet waste:	3527
Waste generation	Hazardous waste:	No
in the operation Phase:	Biomedical waste (If applicable):	No
	STP Sludge (Dry sludge):	95 Kg/day
	Others if any:	E waste - 4000-5000 Kg/annum
	Dry waste:	will be handed over to NMC
	Wet waste:	will be treated in Smart OWC
	Hazardous waste:	NA
Mode of Disposal of waste:	Biomedical waste (If applicable):	NA O
	STP Sludge (Dry sludge):	will be used as manure
	Others if any:	E waste - Will be handed over to authorized vendor, if any
	Location(s):	Near Building H & Amenity
Area requirement:	Area for the storage of waste & other material:	195 + 91 m2
	Area for machinery:	50 Sq. mtr.
Budgetary allocation (Capital cost and	Capital cost:	Rs. 60.50Lacs
O&M cost):	O & M cost:	Rs. 16.84 Lacs/year

Page 5 of 14

	29.Effluent Charecterestics							
Serial Number	Parameters	Unit	Unit Inlet Effluent Outlet Effluent Effluent Charecterestics Charecterestics star					
1	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable			
Amount of e	Amount of effluent generation (CMD):		Not applicable					
Capacity of	the ETP:	Not applicable						
Amount of trecycled:	reated effluent	Not applicable						
Amount of v	water send to the CETP:	Not applicable						
Membership of CETP (if require):		Not applicable						
Note on ETP technology to be used		Not applicable						
Disposal of	the ETP sludge	Not applicable						



	30.Hazardous Waste Details					etails			
Serial Number	Descr	ription	Cat	UOM	Existing	Proposed	Total	Method of Disposal	
1	Not ap	oplicable Not applicable		Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	
			31.St	acks em	ission D	etails			
Serial Number	Soction At limite			ed with ntity	h Stack No. Height from ground level (m)		Internal diameter (m)	Temp. of Exhaust Gases	
1	DG se	et 380	311.6	Kg/hr	5	15 m	300	475	
2	DG se	t 1500	984 I	Kg/hr	4	15	300	525	
3	DG se	et 400	65.6	Kg/hr		15	300	475	
		7	32.De	tails of I	uel to b	e used			
Serial Number	Туг	e of Fuel	7:49	Existing	9	Proposed	2	Total	
1		Diesel	0	Diesel		Diesel	V	Diesel	
33.Source o	f Fuel	3	Autho	orized Deale:		3			
34.Mode of	Transportat	tion of fuel to	site By ro	ad 💮	304	1 7	H		
			X	A DA	Pa F	ý	13		
		田	H	35.Eı	nergy	dr.	H		
		Source of supply:	7	MSEDCL					
		During Co Phase: (De Load)		280 KVA					
		DG set as back-up de constructi	uring	65 KVA					
		During Opphase (Conload):		Residential - 15MW Commercial - 12637 kW					
Pov require	-	During Op phase (De load):		Residential - 15MW Commercial - 12637 kW					
		Transform	er:	Residential kVA	15 nos. x 63	0 kVA , Com	mercial 2 X	2500 kVA, 2 X 1600	
	DG set as Power back-up during operation phase		uring	Residential 5nos x 380 kVA, Commercial 4 X 1500 kVA ,1 X 400 kVA					
Fuel used:			Diesel						
	Details of high tension line passing through the plot if any:								
		Ener	gy saving	j by non-	-convent	ional me	thod:		
Solar panels	s & solar wa	iter heating i	s provided						
	36.Detail calculations & % of saving:								

Page 7 of 14

Serial Number	E	nergy Cons	ervation Measures		Saving %		
1	Use of CFI	_ / LED lamp	s in all public/ common a	reas.	86 %		
2		Solar power	red water heating.		100 %		
3	El	ectronic V3F	F Drives for Elevators	Yes	, all lifts are V3F Drivers		
4	Solar Pan	el & stand al	lone pole will be provided villas	l for	6.18%		
		37	.Details of pollut	ion control Syste	ems		
Source	Ex	isting pollu	tion control system	Pro	oposed to be installed		
STP			1		2		
OWC			1	M	1		
DG Set			2	1(())7///	8		
(Capital	allocation cost and	Capital co	41112	r Heating Rs. 376.56 lac r Heating Rs. 3.93 Lacs	s + solar panel Rs. 5.56 Lacs		
	cost):	O & M cos		2	//		
38	Environ	onmen	tal Manageme	ent plan Budg	jetary Allocation		
		a)	Construction pha	se (with Break-	up):		
Serial Number	Attri	butes	Parameter	Total Cost	per annum (Rs. In Lacs)		
1	A	ir 🐪	Water For Dust Suppression		3.07		
2	Air		Air & Noise Monitoring	1.34			
3	Wa	nter	Tanker Water For Construction		3.2		
4	Wa	nter Z	Water Monitoring	0.42			
5	La	ind	Site Sanitation- Mobile toilets	13.65			
6	Biolo	ogical	Gardening Set Up and top soil preservation	106.8			
7		conomic onment	Disinfection- Pest Control		0.24		
8		conomic onment	First Aid Facilities	Men	0.45		
9		conomic onment	Health Check Up		5.6		
10		conomic onment	Creches For Children	asni	36.5		
11		conomic onment	Personal Protective Equipment	3.0116	4.2		
		b) Operation Phas	e (with Break-up	p):		
Serial Number	Comp	onent	Description	Capital cost Rs. In Lacs	Operational and Maintenance cost (Rs. in Lacs/yr)		
1		Treatment ant	3 no STP	Rs. 194.20	Rs. 39.42		
2	Rain Water	Harvesting	8 tanks with 3 borewell each	Rs. 84.00	Rs. 2.50		
3		Waste gement	2 no OWC will be provided	Rs. 58.8	Rs. 18.20		

Page 8 of 14

4	Green Belt Development	RG will be provided	Rs. 336.00	Rs.30.00
5	Energy Use (Solar panel)	Energy saving	Rs. 2.64	Rs. 0.13
6	Energy Use (Solar water heating)	Energy saving	Rs. 371	Rs. 3.71
7	Solar Lighting for villa	Energy saving	Rs. 2.92	Rs. 0.09
8	Environmental Monitoring	EMP costing	MoEFCC approved laboratory	Rs. 25.88
9	Swimming Pool	Swimming Pool	Rs. 37.00	Rs. 1.8
10	Basement Ventillation	Basement Ventillation	Rs. 377	Rs. 7.54
11	Basement Dewatering	Basement Dewatering	Rs. 32.50	Rs. 3.25
12	Total	Total	1496.06	132.52

39.Storage of chemicals (inflamable/explosive/hazardous/toxic substances)

Description	Status	Location	Storage Capacity in MT	Maximum Quantity of Storage at any point of time in MT	Consumption / Month in MT	Source of Supply	Means of transportation
Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable
	40.Any Other Information						

No Information Available

Government of Maharashtra

CRZ/ RRZ clearance obtain, if any:	No
Distance from Protected Areas / Critically Polluted areas / Eco-sensitive areas/ inter-State boundaries	None within 10 km
Category as per schedule of EIA Notification sheet	8 (b) B1
Court cases pending if any	S.No. Details Case Number Case detail 1 Ratan Madan v/s GIPL 931/13 State Forum 2 GIPL v/s AvinashChaurasia 445/15 Civil 3 GIPL v/s AvinashChaurasia 203/16 Civil 4 Sanjay Bhansali v/s GIPL 774/15 State Forum 5 YugalKishorBhattad v/s GIPL 773/15 State Forum 6 Meena Soni v/s GIPL 15/15 Consumer Forum 7 GIPL v/s KrushnaKadu145/16 State Forum 8 GIPL v/s Kamlesh Shah 272/15 Civil 9 GIPL v/s Kamlesh Shah 106/14 Civil
Other Relevant Informations	depth of Existing pond of 60m x 60m x 5m to be reduced to 60m x60m x 1.25m for safety purpose
Have you previously submitted Application online on MOEF Website.	No No
Date of online submission	

3. The proposal has been considered by SEIAA in its 139th meeting & decided to accord environmental clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implementation of the following terms and conditions:

Specific Conditions:

I	PP to submit ground coverage foot print for existing and proposed development.
II	PP to submit conceptual as well as sanction plan submitted for earlier EC.
III	PP to submit details for CER activities
	PP to submit revised CER as per MoEF&CC circular dated 1.5.2018 relevant to the area and people around the project to Principal Secretary, Environment Department, GoM for approval.

General Conditions:

I	E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
п	The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
Ш	This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.
IV	PP has to abide by the conditions stipulated by SEAC& SEIAA.
v	The height, Construction built up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body & it should ensure the same along with survey number before approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.
VI	If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
VII	All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.

VIII	Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
IX	The solid waste generated should be properly collected and segregated. dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
X	Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
XI	Arrangement shall be made that waste water and storm water do not get mixed.
XII	All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
XIII	Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
XIV	Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
XV	Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
XVI	Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate watercourses and the dumpsites for such material must be secured so that they should not leach into the ground water.
XVII	Any hazardous waste generated during construction phase should be disposed off as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
XVIII	The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
XIX	The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from concern authority shall be taken.
XX	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
XXI	Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
XXII	Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27th August, 2003. (The above condition is applicable only if the project site is located within the 100Km of Thermal Power Stations).
XXIII	Ready mixed concrete must be used in building construction.
XXIV	Storm water control and its re-use as per CGWB and BIS standards for various applications.
XXV	Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
XXVI	The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
XXVII	The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treatment of 100% gray water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP.
XXVIII	Permission to draw ground water and construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
XXIX	Separation of gray and black water should be done by the use of dual plumbing line for separation of gray and black water.
XXX	Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
XXXI	Use of glass may be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.
XXXII	Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.

XXXIII	Energy conservation measures like installation of CFLs /TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible like installing solar street lights, common solar water heaters system. Project proponent should install, after checking feasibility, solar plus hybrid non-conventional energy source as source of energy.
XXXIV	Diesel power generating sets proposed as source of backup power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
XXXV	Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
XXXVI	Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
XXXVII	Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspiration for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.
XXXVIII	The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.
XXXIX	Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.
XL	Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
XLI	Six monthly monitoring reports should be submitted to the Regional office MoEF, Bhopal with copy to this department and MPCB.
XLII	Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.
XLIII	Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.
XLIV	Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.
XLV	A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB.
XLVI	In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Department.
XLVII	A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
XLVIII	Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB & this department.
XLIX	The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at http://ec.maharashtra.gov.in.
L	Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
LI	A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.

Page 12 of Shri. Anil Diggikar (Member Secretary SEIAA)

LII	The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM. SO2, NOx (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
LIII	The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
LIV	The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
LV	SEIAA decided to grant EC for- FSI area: 206179.00 m2, Non FSI area: 273193.00 m2 and Total BUA: 479372.00 m2.



- 4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.
- 5. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
- 6. The Environment department reserves the right to add any stringent condition or to revoke the clearance if conditions stipulated are not implemented to the satisfaction of the department or for that matter, for any other administrative reason.
- 7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, and amendments by MoEF&CC Notification dated 29th April, 2015.
- 8. In case of any deviation or alteration in the project proposed from those submitted to this department for clearance, a fresh reference should be made to the department to assess the adequacy of the condition(s) imposed and to incorporate additional environmental protection measures required, if any.
- 9. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
- 10. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1stFloor, D-, Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Shri. Anil Diggikar (Member Secretary SEIAA)

Copy to:

- 1. SECRETARY MOEF & CC
- 2. IA- DIVISION MOEF & CC
- 3. MEMBER SECRETARY MAHARASHTRA POLLUTION CONTROL BOARD MUMB
- 4. REGIONAL OFFICE MOEF & CC NAGPUR
- 5. MUNICIPAL COMMISSIONER NAGPUR
- 6. REGIONAL OFFICE MPCB NAGPUR
- 7. REGIONAL OFFICE MIDC NAGPUR
- 8. MAHARASHTRA STATE ELECTRICITY DISTRIBUTION CO. LTD
- 9. COLLECTOR OFFICE BHANDARA
- 10. COLLECTOR OFFICE NAGPUR
- 11. COLLECTOR OFFICE WARDHA

12. COLLECTOR OFFICE GADCHIROLI